

City of Oakley
ADDENDUM NO. 3 to contract documents for
CIP 247 – East Cypress Road Widening Project From Knightsen
Avenue to Jersey Island Road

REVISED BID OPENING DATE: October 14, 2022 - 2:00 PM

Notice is hereby given that the following clarifications and revisions are made to the above referenced contract documents:

All bidders shall acknowledge receipt and acceptance of Addendum No. 3 by signing in the space provided at the end of this Addendum and submitting the signed addendum with their proposal.



Jason Kabalin
Capital Projects Engineer
October 10, 2022

Contractor Signature

Date

Company Name

I. Updates to the Part I of the Specifications:

NOTICE TO CONTRACTORS

Sealed proposals will be received at the office of the City Clerk of the City of Oakley, 3231 Main Street, Oakley, CA 94561, until

2:00PM

FRIDAY

OCTOBER 14, 2022

for the following project:

**CIP 247 – EAST CYPRESS ROAD WIDENING
FROM KNIGHTSEN AVENUE TO JERSEY ISLAND ROAD**

at which time they will be publicly opened and read aloud. Sealed proposals must be clearly marked on the outside with the Project number, date, and time of bid.

II. Updates to the Part III of the Specifications:

- 1. Replace 2nd paragraph language in Section 10-1.16 EARTHWORK under GENERAL heading with the following:**

Earthwork shall conform to the Project Geotechnical Report included in Appendix A prepared by Cal Engineering and Geology dated March 30, 2022 – Geotechnical Design Report – East Cypress Road Widening Project, and to the provisions in Section 19, "Earthwork," of the Standard Specifications and these technical specifications.

- 2. Replace 2nd paragraph language in Section 10-1.16 EARTHWORK under Materials, General subsection with the following:**

General

Excavated material that is suitable for fill construction shall be conditioned for reuse and properly stockpiled for later filling and backfilling operations. Conditioning shall consist of spreading material in layers not to exceed 8 inches and raking free of debris and rubble. Rocks exceeding 3 inches in largest dimension, unsuitable material and deleterious material shall be removed from the site and disposed of as specified herein under Disposal of Surplus Material.

- 3. Delete the language in Section 10-1.16 EARTHWORK under Materials, Fill and Backfill subsection and replace with the following:**

Fill and Backfill

~~Well to moderately well-graded soils consisting of sands, silts, and clays, with or without gravel, as excavated, screened or blended, having the following mechanical properties and gradation:~~

~~1. Gradation (ASTM D422)~~

Sieve Opening	Percent Passing by Weight
6-inch Square	100
3/4-inch Square	70 min

~~2. Liquid Limit (ASTM D4318): 50 max~~

~~3. Plasticity Limit (ASTM D4318): 25 max~~

Refer to Section 6.1.6 Material for Engineered Fill of the Project Geotechnical Report, see Appendix A.

4. Replace the following Pay Clause in Section 10-1.29 – Sanitary Sewer Force Main Improvements under Measurement and Payment

VERTICAL OFFSET ON SEWER FORCE MAIN PIPE shall be at the cost indicated in the Bid Schedule. The contract lumpsum price paid for VERTICAL OFFSET ON SEWER FORCE MAIN PIPE shall include, but is not limited to, full compensation for furnishing all labor, materials, tools, equipment and incidentals required for doing all the work involved with installing new 14" PVC C900 DR14 sewer force main with horizontal and vertical bends around the proposed storm drainage main, maintain existing sanitary sewer flows during construction, [optional sewer bypass to Bethel Island Road and East Cypress Road intersection northwest corner, sewer bypass discharge and clean up fees and coordination with Ironhouse Sanitary District for sewer bypass](#), trenching and excavation, over excavation, dewatering, bedding, coarse bedding material in geotextile wrap with 12 min. overlap at fabric edges, backfill, warning tape, submitting compaction reports, thrust blocks and mechanical restraints, and pavement restoration to finish grade, as shown on the Plans, as specified in the Standard Specifications, these Technical Specifications and the Special Provisions, and as directed by the Engineer. Additionally, no payment will be made for work, equipment, or materials not covered in these plans and specifications, but necessary to insure a completed project as specified.

III. Updates to the Plan Sheets:

1. Replace Detail 7 on Sheet 10, G1.9 with the following

